KRISHNARAJENDRA HOSPITAL, MYSORE.

Notice dated 3rd October 1931.

Notice is hereby given that sealed tenders on half-sheet of Foolscap sized paper in triplicate will be received at the office of the Dubar Surgeon and Medical Officer, Krishnarajendra Hospital, Mysore, by the Durbar Surgeon and Medical Officer at 11 A.M., on Sunday the 1st November 1931, for the supply of Pasteurised Milk (as per list annexed) required for the use of the Krishnarajendra Hospital, Mysore from 1st January 1932 to 31st December 1932 (Inclusive).

2. No tender will be received after the date and hour abovementioned.

3. Tenders to be superscribed "Tender for the supply of Pasteurised Milk" to the Krishnarajendra Hospital. Mysore.

4. No tender will be received unless accompanied by a deposit of Rs. 100, for pasteurised milk in treasury receipt. No cash payment will be received.

5. Tenders will be opened by the Durbar Surgeon and Medical Officer in charge, at his office (Krishnarajendra Hospital, Mysore) on the day and hour abovementioned in the presence of such tenderers as may choose to attend.

6. The rate must be specified in figures as well as in words. The value of each tender must be worked out according to the rate tendered and the total value must aslo be entered in words in ink. Tenders not conforming to this rule will be rejected.

7. The quantities stated in the list are not guaranteed.

8. The rate should be quoted in terms of pint (pint=20 ounces) per rupee and not stated in pounds.

9. The deposit of the successful tenderer will be retained and will be forfeited to Government, if he fails to complete the contract by executing the necessary agreement and furnishing the required security (to the amount of Rs. 500) for pasteurised milk within three days from the date of his receiving the intimation of the acceptance of his tender.

10. The Medical Officer reserves to himself the right of rejecting any tender without assigning any reasons therefor.

11. The milk shall be supplied in sterilised and sealed containers of the description and size prescribed by the Medical Officer.

12. In the event of the milk being of inferior quality or of failure in the due fulfilment of such conditions as may be laid down in its handling, pasteurisation, bottling and transit, it will be opened to the Medical Officer to levy a fine not exceeding Rs. 50 on each count. If nevertheless there should be continued breach of the conditions or should the supply prove unsatisfactory in any way, the contract will be liable to be terminated without notice. In such an eventuality the contractor shall be bound to make good to Government the loss that may have to be incurred by having to make other arrangements for the supply.

13. Milk should be supplied every day at 5-30 A.M., 9 A.M. and 5 P.M.

Name of the article.	*Quantity required for* 1932.
Pasteurised Milk.	No. 116130 of pints (pint=20 ounces)

J. F. ROBINSON,
Durbar Surgeon and
Medical Officer.

KOLAR DIVISION.

Notice dated 20th September 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 28th November 1931, for Restoring Dod-Holabi Kadadankere Minor Tank Registered No. 129—649 of Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1932.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. to 5 P.M. on office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 120 only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for restoring Dod-Holabi Kadadankere Minor Tank Registered No. 129—649 of Malur Taluk, Kolar District," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenders must quote specific rates for each item of the work both in words and figures.

10. The tenderers standing that the work would be executed at a certain percentage in excess or lower that the estimate rate will not be excepted.

Abstract estimate of quantities for restoring Dod-Holabi Kadadankere Minor Tank Registered No. 129—649 of Malur Taluk, Kolar District.

No.	Items of work	Per	Quantity	Sanctioned		Rate tendered
				Rate	Amount	
				Rs.	Rs.	
1	Earthwork to bund watering and tamping, including lead and lift up 55·00.	C.yd.	4,546	0 4 0	1,137	
2	Ground backing to revetment	,,	285	0 8	143	
3	Turing to bund	S.yd.	3,550	0 1 0	220	
4	Removing and resetting old stone revetment with new jelly backing and wedging.	C.yd.	365	0 12 0	274	
5	New stones revetment with jelly backing and wedging ..	,,	665	1 10 0	1,081	
6	Providing and fixing new grade stone with cutting, figuring and painting with white lead and Japan.	No.	18	1 8 0	27	
7	Providing and fixing index stones with cutting, figuring and painting with white lead and Japan.	,,	18	0 8 0	9	
8	Providing and fixing gauge stones with cutting, figuring and painting with white lead and Japan.	,,	1	10 0 0	10	
9	Registered No. Stone with cutting. figuring and painting with white lead and Japan.	,,	1	3 0 0	3	
10	B. M. Stone with cutting, figuring and painting with white lead and Japan.	,,	2	3 0 0	6	
11	Cutting trunches and grips and removing top soil ..	Grade	16	2 0 0	32	
12	Cutting deep trench in centre of bund for closing leaks with puddle wall and good earth.	Lump sum	Rupees	..	100	
13	Removing jungle and cutting trees with roots entirely gabled up 2005 ant hills and filling with good earth.	Grade	16	2 0 0	32	
	Total to bund ..	..	..	..	3,074	
	SLUICE R. L. 46·00.					
14	Draft clearing up to R. L. 46·00 and using the same to bund ..	..	..	..	..	
15	Earthwork for cut opening the bund	C.yd.	48	0 4 0	12	
16	Refixing the same with watering and tamping	,,	37	0 3 0	7	
17	Gravel backing to revetment and fixing gravel in front slope of bund.	,,	12	0 8 0	6	
18	Stone jelly surki concrete for foundation	C.ft.	250	0 4 0	70	
19	Burnt brick in surki mortar	,,	230	0 5 0	72	
20	Burnt stone slabs 4" to 6" thick	S.ft.	178	0 6 0	67	
21	Plastering with surki mortar	,,	4·00	4 0 0	16	
22	Cutting holes in crass and orifice slabs	No.	3	1 0 0	3	
23	Providing plug and rod with locking arrangements ..	Lump sum	Rupees	..	12	
24	Dismantling the old sluice and refilling the bund with necessary gravel.	Lump sum	Rupees	..	20	
	Total ..	..	..	..	285	
	WEIR R. L. 50·00.					
25	Earthwork excavation	C.yd.	2	0 4 0	1	
26	Benching hard rock for foundation of body wall ..	S.ft.	59	0 12 0	44	
27	Stone jelly concrete for foundation of returns	C.ft.	8	0 4 0	2	
28	Burnt brick in surki mortar	,,	101	0 5 0	31	
29	Burnt stone slabs 4½" to 6" thick	S.ft.	66	0 6 0	25	
30	Cutting joggle joints	Each	5	1 0 0	5	
31	Plastering with surki mortar	Sqr,	1·53	4 0 4	6	
32	Plastering sheet rock in draft approaches	C.yd.	154	2 0 0	308	
33	Providing body wall in uneven places with stone, jelly, surki concrete and cement plastering after blasting rocks.	Lump sum	Rupees	..	15	
	Total ..	..	..	..	437	
	Grand Total ..	..	..	..	3,796	

Dated 8th October 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 7th November 1931, for completing the remaining works on Restoring Gulichikkankunte of Hulaganahalli, Regd. No. 200 of Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th January 1933.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5. P.M., office days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees 175 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Gulichikkan kunte of Hulaganahalli, Regd. No. 200 of Goribidnur Taluk, Kolar District, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderer must quote specific rates for each items of work both in words and figures.

10. The tenders stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate of quantities for completing the remaining works on Restoring Gulichikkankunte of Hulaganahalli, Regd. No. 200 of Goribidnur Taluk.

No.	Items of work	Unit	Quantity	Estimated rate
	Bund.			Rs. a. p.
1	Earthwork including watering and tamping ...	C.yd.	2,734	0 3 0
2	Turfing	S.yd.	4,584	0 1 0
3	Jungle clearing	Lump	sum	...
4	Rough stone work new	C.yd.	358	2 0 0
5	Grade stone with index stones cutting figures painting fixing, etc., complete.	Each	29	3 0 0
6	B M stones, complete	,,	2	3 0 0
7	Gauge stone 15 feet high	,,	1	20 0 0
8	Inscription stone	,,	1	35 0 0
	Sluice.			
9	Earthwork watering and tamping	C.yd.	6	0 3 0
10	Concrete burnt stone jelly mortar	C.ft.	71	0 4 0
11	Burnt stone in surki mortar	,,	14	0 5 0
12	Do slabs 6" thick dressed	S.ft.	43	0 6 0
13	Plastering with surki mortar	Sqr.	0·84	4 0 0
14	Providing and fixing plug with iron rod to the sluice with locking arrangements.	Lump	sum	...
	Left Weir.			
	Earthwork to be used for ring bund ...	C.yd.	253	0 3 0
	Concrete	C.ft.	471	0 4 0
	Burnt brick in surki mortar	,,	1,205	0 5 0
	Burnt stone slabs 6" thick dressed	S.ft.	441	0 6 0
	Plastering with surki mortar	Sqr.	17·08	3 8 0
	Burnt stone jaggle	Each	44	1 0 0
	Rough stone work new	C.yd	127	2 0 0
	Right Weir.			
	Earthwork to be used for ring bund	,,	..	0 3 0
	Concrete	C.ft.	63	0 4 0
	Burnt brick in surki mortar	,,	47	0 5 0
	Burnt stone slabs 6" thick dressed	S.ft.	174	0 6 0
	Plastering with surki mortar	Sqr.	9·54	3 8 0
	Burnt stone jaggles	Each	33	1 0 0
	Rough stone work new	C.yd.	156	2 0 0
	Old stone work with jelly	,,	22	0 10 0
	(Stones have been removed—they have to be refixed with jelly.)			

C. T. NARASIMHA IYENGAR,
Executive Engineer.